BRUHAT BANAGLORE MAHANAGARA PALIKE

EXTRA ITEM RATE LIST

Name of Work: Providing Children Play Equipments and Senior Citizen Gym Equipments and Landscape Development in Parks in Ward no. 07, Kodigehalli of Yelahanka Zone

Sl No	Item Of Work	Unit	Estimate qty	Rate in Rs. Considering 2016-17	Amount (Rs.)	Whether the item alternative to tender or additional items	Whether the extra item is included in sanctioned estimate	How the Cost is proposed to be met	Whether extra item is included in S.R.	Remarks
1	2	3	4	5	6	7	8	9	10	11
1	Supply and Fixing of HD set up station : Metal All tubular steel of 2.5mm thickness are galvanized and zinc dipped joints are robotic welded. joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc primer paint is applied to all the welding points prior to finishing. all metal parts are powerded coated using AXZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metalk parts aare tested in our salt spreay machine that uses a 5% NaCl solution in accordance to IS07227 to speed up corrosion for 3000hrs. Rubber High Quality grip runbber is used for the handles, bearings, Maintaenence-free ball bearing. Scope of delivery: 1 Completely pre-assembled equipment modules. maintanance. Maintain according to EN 16630 and the maintainance guide. safety, all products must be tested and certified to meet EN16630 safety standards with GS test mark the EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only,. The GS Mark. EN16630 certificates, Size L x W x H) : 1412 x 1366 x 650mm. Weight: 42.6Kg safety Area: 4462 x 4078 mm Capacity 2	Unit	2.00	147950.00	295900.00	Additional item	No	-		Approved Data Rate
2	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (SR 2016-2017, Page 23, Item No 5.9)	Cum	90.59	5459.45	494571.94	Additional item	No	-		Yes (SR 2016-2017, Page 23, Item No 5.12)
	TOTAL EIRL AMOUNT				790472.00					

PERCENTAGE OF EXCESS COMPARING TO SANCTIONED COST= $\frac{790472.00}{10880101.05}$ x100 = 7.27%

Assistant Engineer
Project Division
14/10/19

Assistant Executive Engineer
Project Division
14/10/2019

Executive Engineer
Project Division
14/X/19

"EIRL Approved"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ